

FRONT ELEVATION



SIDE ELEVATION



SECTION 'C' – 'C'



MOUNTING DETAIL FOR FLOAT SWITCH

SCALE 1 : 5



P L A N

SCALE 1:10



SECTION 'A' – 'A'



SECTION 'B' – 'B'

(NUTS REMOVED ON THIS VIEW)



DETAIL OF ø50mm STANDARD PIPE SOCKET CONNECTION

SCALE 1 : 2



DETAIL OF HANDHOLE COVER

SCALE 1 : 5



DETAIL OF M.S. TANK PAD FOR LEVEL DIAL MAGNETIC CONTENTS GAUGE

SCALE 1 : 2

(MANUFACTURER TO BE ADVISED OF TANK DIMENSIONS WHEN PLACING ORDER) (DIAL CALIBRATION–FRACTIONS OF CAPACITY)

NOTES:

1. ALL WELDING SHALL BE CARRIED OUT IN ACCORDANCE WITH THE BRITISH STANDARDS AS APPROPRIATE AND SHALL BE TO THE ENTIRE SATISFACTION OF THE ENGINEER.
2. ALL SOCKETS TO BE PROVIDED WITH ADAPTOR BUSH. UNUSED SOCKETS TO BE PLUGGED UP BY BRASS PLUG.
3. ALL JOINTS ON STEEL PAD CONNECTIONS TO BE FITTED WITH 3mm THICK OIL RESISTANT GASKETS.
4. ALL ELECTRIC LEVEL SWITCHES SET TO WORK FOR HIGH LEVEL, LOW LEVEL, 6.5–HOUR AND 7–HOUR LEVEL CONTROL VOLTAGE SHALL NOT BE GREATER THAN 50 V.
5. PIPEWORK SHALL BE TO B.S. 1387 GRADE C, FLANGES OR SOCKETS SHALL BE PROVIDED WHERE NECESSARY FOR EASE OF DISMANTLING.
6. THE TANK AND THE PIPEWORK SHALL BE HYDRAULICALLY TESTED TO A PRESSURE OF 70kPa AND 700kPa RESPECTIVELY.
7. ALL STEEL WORK, M.S. ANGLE STAND AND M.S. OIL TRAY, INCLUDING THE EXTERIOR SURFACES OF SERVICE TANK SHALL BE PAINTED WITH ONE COAT OF BEST QUALITY PRIMER & TWO COATS OF BEST QUALITY BROWN PAINT (06 C 39 TO B.S. 4800 OR EQUIVALENT).
8. THE INTERIOR SURFACES OF SERVICE TANK SHALL BE TREATED WITH ONE COAT OF OIL RESISTANT PRIMER.
9. ALL DIMENSIONS IN mm UNLESS OTHERWISE STATED.

no.	date	description	initial
REVISION			

	name	date
designed		
checked	W.S. TAM STO/DP7	10/2004
drawn	C.S. CHOI TO/DP7/1	10/2004
approved	Y.M. LI SPE/7	
contract no.		
file no.	DP 10103	
project no.		
contract	REFERENCE DRAWING	
drawing title	1000 LITRE DIESEL FUEL OIL SERVICES TANK	
drawing no.	P–10243–011–A	
scale	AS SHOWN	

PROJECT DIVISION

機電工程署 EMSD

Section: DP7 Division: P.D.

A0 1198 x 841

Drawing Reference: P10243d001011.dwg Ref. drawings: FORM A87–A0