



Implementation of District Cooling System at Kai Tak Development

MA Chun-yue
Engineer, Energy Efficiency Office
Electrical and Mechanical Services Department

23 September 2014

Content





- What is District Cooling System (DCS)
- Benefits of DCS
- Background and Implementation
- Major Facilities
- Construction/Current Status of the Project
- Q & A

珍惜資源
全民節能

What is District Cooling System




- Supply chilled water to more than one building through distribution networks



What is District Cooling System




- Major components include:
 - Central chiller plants
 - Underground distribution networks
 - Heat exchangers





Benefits of DCS

- Save energy compared with traditional A/C systems in individual buildings





Benefits of DCS

- Annual energy saving of up to 85 million kWh or equivalent to the reduction of 59,500 tonnes CO₂ emission upon full development

120 Victory Park
2 million trees





Benefits of DCS

- More adoptable than individual system to varying demand for air-conditioning
- Noise, vibration and heat arising from individual plant could be reduced



Benefits of DCS

- Enhance building/architectural design/function, better planned maintenance, reduce heat island effect, etc.






Background and Implementation

- Total design cooling capacity: 284 MW
 - North Plant cooling capacity: 162 MW
 - South Plant cooling capacity: 122 MW
- Total pipe-run length: around 40 km
- Expected number of users: around 60

珍惜資源 全民節能

Background and Implementation



Background and Implementation



- Phase I – pipes laying works, commenced in Feb 2011, substantially completed in Jan 2013
- Phase II – DBO contract, commenced in Mar 2011, target completion by end 2014
- Phase III (A) – commenced in July 2013, target completion by 2017

珍惜資源
全民節能

Background and Implementation



- Phase III (remaining) – to suit the actual schedule of KTD (up to around 2021)
- Operation commenced since Feb 2013 (2/2013 for Kai Tak Cruise Terminal and 5/2013 for shopping centre of public housing)
- Coming users: Hong Kong Children Hospital, Trade and Industry Tower, MTR Kai Tak Station and To Kwa Wan Station and Kowloon East Regional Headquarters and Operational Base cum Ngau Tau Kok Divisional Police Station

Background and Implementation




NORTH PLANT			
Phasing	Cooling Capacity (kW)	Chillers Configuration	
		Cooling Capacity (kW)	Quantity
Phase I & II	11,600	4,390	2
		1,410	2
Phase III (Package A)	17,584	8,792	2
Phase III (Remaining)	140,680	17,585	8

Background and Implementation



SOUTH PLANT			
Phasing	Cooling Capacity (kW)	Chillers Configuration	
		Cooling Capacity (kW)	Quantity
Phase I & II	17,390	4,390	3
		2,110	2
Phase III (Package A)	35,170	17,585	2
Phase III (Remaining)	70,339	8,792	2
		17,585	3

Background and Implementation




Major Facilities - North Plant




- Box culvert at centre of site
- The landscape area maximized with Green roof

Major Facilities - North Plant






- Plant Room Area
- Internal Circulation




Major Facilities - South Plant



Residential Site



Major Facilities - South Plant



Major Facilities – Customer Substation




- Normally, one sub-station per building to house two heat exchangers



Construction – North Plant



Construction – South Plant



Construction - Pipeworks



Current Status - North Plant



Current Status - North Plant



Current Status - North Plant



Current Status - South Plant



Current Status - South Plant





Q & A

Thank You!

珍惜資源
全民節能