



# Topics

## Common irregularities

1. Stage One Declaration
2. Stage Two Declaration
3. Form of Compliance
4. Energy Audit submission

珍惜資源  
全民節能



# Stage One Declaration

- Deliver to the EMSD's office within **2 months after the day on which the consent to the commencement of building works for the superstructure construction** is given:



## Example

- Consent date: 05 September 2015
- Submission Date: 04 November 2015
- i.e. the declaration is arrived at the EMSD's office on or before 04 November 2015



# Stage One Declaration (Cont'd)

- Consent Issue date: the one in Form BD103
- Submit a copy of Form BD103 also
- Both the developer and REA to sign with dates on the declaration form

Form BD 103

Issue date of the consent

Form BD103 (Continued)

Our Ref. No.	Type of Plans	Date of Notice of Approval	Consent Date	Name, Post & Signature	Consent Renewal Date	Name, Post & Signature
BD 2/4016/10	Building Amendment# (Ground beams and slabs only)	3 April 2013	13 May 2013			
BD 2/4016/10	Building#	30 April 2010	14 May 2013			
BD 2/4016/10	Building Amendment#	4 April 2011, 20 January 2012, 31 August 2012, 17 October 2012, 12 December 2012, 8 February 2013, 3 April 2013				
BD 4/4016/10	Drainage#	22 November 2012				
BD 4/4016/10	Drainage Amendment#	17 January 2013, 23 April 2013				
BD 3/4016/10	Superstructure (above Ground Floor) #(Remaining Portion)	22 April 2013				

# Stage One Declaration (Cont'd)



- Outdated Form EE1 and EE-SU
- ✓ Updated Form EE1 and EE-SU uploaded in BEEO website

Buildings Energy Efficiency Ordinance

機電工程署 EMSD

ENG 繁體

HOME CONTACT US SITEMAP DISCLAIMER

Enter search keyword(s)

### Buildings Energy Efficiency Ordinance (Cap 610)

ABOUT REVISIONS CIRCULAR REGISTER & LIST REGISTERED ENERGY ASSESSOR (REA) PUBLICITY FAQs USEFUL LINKS

#### Forms

Forms for the Ordinance

Form No.	Type of Form	Download
EA1	New Application / Renewal Application / Change of Particulars for Registration as Registered Energy Assessor (Rev. 03/15)	(1.34MB) [PDF format]
EA2	Application for Duplicate of Certificate of Registration - Registered Energy Assessor	(381KB) [PDF format]
EA3	(New / Change of Particulars of Registered Energy Assessor) Application for Registration of Public Officer as Registered Energy Assessor (Rev. 03/15)	(826KB) [PDF format]
EE1	Stage One Declaration (Rev. 11/13)	(259KB) [PDF format]
EE2	Stage Two Declaration (Rev. 11/13)	(263KB) [PDF format]
EE3	Application for Renewal of Certificate of Compliance Registration (Rev. 11/13)	(248KB) [PDF format]
EE4	Form of Compliance (Rev. 11/13)	(268KB) [PDF format]

[http://www.beeo.emsd.gov.hk/en/mbec\\_forms.html](http://www.beeo.emsd.gov.hk/en/mbec_forms.html) [25/11/2015 15:15:52]

# Stage One Declaration (Cont'd)



- Incorrect BEC edition on P.2/6 and 3/6 of Form EE1
- ✓ Developer's signature date on or after 28 Aug 2014  
**BEC 2012 (Rev.1)**

Section B 乙部 : Declaration 聲明

To: The Director of Electrical and Mechanical Services  
致: 機電工程署署長

1. In accordance with section 8 of the Buildings Energy Efficiency Ordinance (Chapter 610), we, as the Developer, declare that all building services installations to be provided by us in the building described in section A of this form (see note 4) at or before the time when a stage two declaration is made in respect of the building(s) / development are designed, and will be installed and completed, in accordance with the specified standards and requirements not lower than the Code of Practice for Energy Efficiency of Building Services Installations (year) \_\_\_\_\_ Edition.


We also declare that all the information reported in this form and in all the attachments is true and correct.  
根據建築物能源效益條例（第610章）第8條，我們作為發展商，現聲明本表格甲部所述的建築物在作出次階段聲明之時或之前由我們在該建築物內提供的所有屋宇裝備裝置（見須知事項4），均按照不低於《屋宇裝備裝置能源效益實務守則》（版本見上述英文段落）的指明標準及規定設計，並將會按照該等標準及規定設計及完成。  
我們亦聲明在本表格填報及所有附件內的一切資料全屬真確無訛。

Company Name of Developer 發展者公司名稱	English 英文	_____
	Chinese 中文	_____
Representative Person (if any) 代表人（如有）	Salutation 稱謂	Mr. / Miss / Ms.* 先生 / 小姐 / 女士 *
	English Name 英文姓名	_____

# Stage One Declaration (Cont'd)



- Date of declaration of REA should be indicated in on page 2/11 of Form EE-SU



Date of Declaration by Registered Energy Assessor in Form EE1 / EE2 / EE3 / EE4 \*:  
載於表格 EE1 / EE2 / EE3 / EE4 \* 之能源效益評核人的聲明日期:

\_\_\_\_\_

Is this submission to supersede a form submitted before? (Please give a "✓" in the appropriate box)  
此次提交是否代替之前所提交之表格? (請於適當空格內加上「✓」號)

Yes 是                       No 否  
(If no, please ignore the following two items.)  
(如否, 請不必理會以下兩項。)

If EMSD's reference no. for the form submitted before is known, please provide:  
如知悉有關之前所提交之表格的機電工程署檔號, 請提供:

\_\_\_\_\_

Otherwise, please provide the date of declaration by Registered Energy Assessor in the previous form:  
否則, 請提供能源效益評核人於之前表格的聲明日期:

\_\_\_\_\_

# Stage One Declaration (Cont'd)




- Separate submission of Form EE1 and EE-SU for multi-blocks development

## 4.2.7.1 COCR Per Podium Tower Pair

For a building complex consisting of a podium block and a single tower block, as shown in TG Figure 4.2.7.1, the complex is normally regarded as a single building block requiring a single COCR and thus single stage one and stage two declarations.


Figure 4.2.7.1 : Building complex with a podium and a tower counted as a single block



## 4.2.7.2 COCR Per Building Block

For a building complex consisting of three blocks, namely tower 1, tower 2 and podium, as shown in TG Figure 4.2.7.2, a COCR should be obtained for each building block, namely for podium block, tower 1 block and tower 2 block, that is a total of 3 nos.

Figure 4.2.7.2 : Two towers with common podium counted as 3 nos. building blocks





# Stage One Declaration

## Provide Supplementary Information

- Site Location Plan;
- Master layout plan; (no. of building blocks)
- Documents/plans about common areas especially for residential and industrial building
- General building layout plans (extent of applicability)
- Document showing the identity of developer (e.g. document from Land Registrar)





# Stage Two Declaration

珍惜資源  
全民節能

# Stage Two Declaration (Cont'd)



## Technical Forms

(Please refer to Section 5, Code of Practice for Energy Efficiency of Building Services Installation 2012 Edition)

Part 2 – Lighting Power Density & Lighting Control Worksheet								
Please provide information in table below for spaces governed by the lighting power density requirement (LPD) and/or the lighting control requirement (BEC Clause 5.4 & Clause 5.5)					Requirements on LPD and no. of lighting control points in BEC (Clauses 5.4 & 5.5.1)			Lighting control   lighting to which applicable are in those for the oth which the Ordina applicable ? (BEC (please tick wh
Drawing No. of lighting layout	Name of space / Space Ref. No. *1	Area of space (m <sup>2</sup> )	Installed LPD *2 (W/m <sup>2</sup> )	Installed no. of lighting control points *3	LPD in BEC Table 5.4		Min allowed no. of lighting control points in BEC Table 5.5*3	
					Applicable type of space *4	Max allowed W/m <sup>2</sup>		
( Please insert additional row if necessary )								
AGR-LTG-01	Disable Lav (<100W)	5.30	5.30	N/A	Toilet	N/A	N/A	<input type="checkbox"/> Yes
AGR-LTG-01	Male Lav(<100W)	5.90	4.70	N/A	Toilet	N/A	N/A	<input type="checkbox"/> Yes
AGR-LTG-01	Female Lav(<100W)	2.70	10.40	N/A	Toilet	N/A	N/A	<input type="checkbox"/> Yes
AGR-LTG-01	Management office(Bareshell)	132.00	1.90	N/A	Bare shell for future fit-out	N/A	N/A	<input type="checkbox"/> Yes
AGR-LTG-01	Water Tank pump rm(<100W)	40.00	2.10	N/A	Plant Room	N/A	N/A	<input type="checkbox"/> Yes
AGR-LTG-01	FS Pump Room (<100W)	20.00	2.80	N/A	Plant Room	N/A	N/A	<input type="checkbox"/> Yes
AGR-LTG-01	LV Switch Room	80.00	1.75	N/A	Switch Room	12.00	N/A	<input checked="" type="checkbox"/> Yes
AGR-LTG-01	U/G HR Pump Rm (<100W)	33.00	1.70	N/A	Plant Room	N/A	N/A	<input type="checkbox"/> Yes
								<input type="checkbox"/> Yes
								<input type="checkbox"/> Yes

- Specified Form carrying legal effect
- Not the REA's capacity to state the applicability

# Stage Two Declaration (Cont'd)



- Provide drawings of proper size to ensure that the content is legible.
- Spaces provided with minimum lighting level to OP inspection only:
  - Should be highlighted and listed;
  - Lighting control points to be provided for office space (reduced no. of lighting control points to reduced LPD refer to TG)

珍惜資源  
全民節能

# Stage Two Declaration (Cont'd)




- Re-submission:
  - REA to provide statement that the submitted material had been reviewed to his satisfaction;
  - or sign the cover letter
- Belated resubmission will render the entire stage two declaration being rejected.

珍惜資源  
全民節能

# Stage Two Declaration (Cont'd)

Special cases for discussion:



- Decorative lighting at ceiling panels solely for decoration purpose?

# Case study




For the sole use as decorative light?

Not from:

- type of luminaire
- statement or declaration from the designer;
- provided with separated circuit/switch


But from the nature and usage:

- the lighting layout (relation w/ other lighting fittings);
- photo (relation w/ the space)



# Case study


- For the sole use as decorative light? (Mirror-wall Interface)
- Please submit drawings to show lightings at vertical plane surface for review



# Case Study

- Connection points (for Total Power Factor and Total Harmonic Devices for circuit at or above 400A missing
- REA/ Designer can choose to provide the connection points at lateral tee-offs or at each distribution boards downstream of tee-off


Figure 7.6 (c) i) : Connection points (for TPF & THD correction devices) for circuit at or above 400 A





# Case Study

- Connection points for Total Power Factor and Total Harmonic Devices for 3-phase circuits each connection to electricity supplier's meter





# Form of Compliance (FOC)

珍惜資源  
全民節能

# FOC (Cont'd)



- Incorrect BEC edition on P3/6 of Form EE4
- ✓ REA's signature date on or after 28 Nov 2014  
**BEC 2012 (Rev.1)**

## Section B 乙部 : Declaration 聲明

To: The above mentioned Responsible Person  
致: 上述的負責人

cc: The Director of Electrical and Mechanical Services, and property management company (or if none, owner)  
副本抄送: 機電工程署署長、及物業管理公司(或如沒有, 則 業主)

In accordance with section 18 of the Buildings Energy Efficiency Ordinance (Chapter 610), I, Registered Energy Assessor, certify that the building services installations in respect of which the major retrofitting works were carried out in the above unit/common area have been designed, installed and completed in accordance with the standards and requirements not lower than the Code of Practice for Energy Efficiency of Building Services Installations (year) \_\_\_\_\_ Edition; and also confirm that I have, in the 30 days before the declaration, personally inspected the building services installations covered by this Form on \_\_\_\_\_ / \_\_\_\_\_ / \_\_\_\_\_ (DD/MM/YYYY) and the results of the inspection are satisfactory.

I also declare that all the information reported in this form and in all the attachments is true and correct.  
根據建築物能源效益條例(第610章)第18條, 本人作為註冊能源效益評核人, 現核證於上述單位/公用地方內進行主要裝修工程的屋宇裝備裝置已按照不低於《屋宇裝備裝置能源效益實務守則》(版本見上述英文段落)的標準及規定設計、裝設及完成; 及確認本人已在作出本聲明之前的30日內, 親自檢查此表格所涵蓋的屋宇裝備裝置(檢查日期見上述英文段落)並滿意檢查結果。  
本人亦聲明在本表格填報及所有附件內的一切資料全屬真確無訛。

Registered Energy Assessor  
註冊能源效益評核人

Salutation  
稱謂  
Mr. / Miss / Ms.\*  
先生/小姐/女士\*

English Name  
英文姓名


# FOC (Cont'd)



**Table 10.1 of the Building Energy Code**

**Form EE-AC and EE-EL should be submitted**

Table 10.1 Major Retrofitting Works and Energy Efficiency Requirements			
Category of Major Retrofitting Work	Condition for Applicability of BEC Requirement	Applicable BEC Requirement	BEC Clause No.
(ii) addition or replacement of a unitary air-conditioner or a chiller of a cooling or heating rating at or exceeding 350kW	applicable in any conditions	air- conditioning equipment efficiency	6.12
	the work involving for the additional or replacement air-conditioning equipment the addition or complete replacement of corresponding water side pumping system	frictional loss of water piping system	6.9
		energy metering	6.13
	ditto, the corresponding water side pumping system forming an independent system	pumping system variable flow	6.8
	the work involving addition or replacement of pipework, ductwork or AHU	thermal insulation	6.11
	the work involving addition or replacement of water pump with new motor, of AHU with new motor, or of fan with new motor	motor efficiency	7.5.1
	in addition to the addition or replacement of the	the work involving addition or replacement of luminaires with a	requirements as for (a) (i)



# FOC (Cont'd)



The works area are < 500m2  
MRW??

Page 4/9 of Form EE-SU

(d) Form 表格 EE4

**Details of major retrofitting works 主要裝修工程的詳情**  
(Please put a "✓" against the appropriate box 請在適當的空格內加上「✓」號)

Location of Works 工程地點	Common Area 公眾地方	Unit 單位	Area of Works (m <sup>2</sup> ) 工程面積 (平方米)	Type of Building Services Installation 屋宇裝備類別	Work Completion Date (DD/MM/YY) 完工日期 (日/月/年)
G/F, North Wing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	216	<input checked="" type="checkbox"/> Lighting 照明 <input checked="" type="checkbox"/> Air Conditioning 空調 <input type="checkbox"/> Electrical 電力 <input type="checkbox"/> Lift & Escalator 升降機及自動梯	22/8/2015
B/F, North Wing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	260	<input checked="" type="checkbox"/> Air Conditioning 空調 <input type="checkbox"/> Electrical 電力 <input type="checkbox"/> Lift & Escalator 升降機及自動梯 <input type="checkbox"/> Lighting 照明	22/8/2015
	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/> Air Conditioning 空調 <input type="checkbox"/> Electrical 電力 <input type="checkbox"/> Lift & Escalator 升降機及自動梯 <input type="checkbox"/> Lighting 照明	/ /
	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/> Air Conditioning 空調 <input type="checkbox"/> Electrical 電力 <input type="checkbox"/> Lift & Escalator 升降機及自動梯	/ /



# FOC (Cont'd)

- Pursuant to section 18(5) of the BEEO, REA issue FOC
  - Send a copy of FOC to DEMS
  - Send a copy of FOC to property management company

(if no such property management company, send the copy to the building owner )

# FOC (Cont'd)

## Form EE-SU



### Section C 丙部: Checklist of Documentary Proof that must be submitted 必須呈交的證明文件清單

I/we attach the copy of the following documentary proof (Must give a tick in all the appropriate boxes):  
本人/我們現附上以下證明文件的副本 (必須在所有適當空格加上✓號):

#### Only applicable to Form EE1 只適用於表格 EE1

- Copy of consent to the commencement of building works (see note 5)  
建築工程展開同意書的副本 (見須知事項5)
- Site location plan / map \* in A3 size  
A3尺寸之工地位置圖/地圖\*

#### Only applicable to Form EE2 只適用於表格 EE2

- Copy of occupation approval (see note 6)  
有關上蓋建築物之「佔用准許」的副本 (見須知事項6)

#### Only applicable to Form EE4 只適用於表格 EE4

- Copy of letter, e-mail or delivery note/receipt etc. to certify that the Form of Compliance has been sent to the responsible person of the relevant building / units  
信函、電子郵件或發送單據/收據等的副本以證明有關遵行規定表格已送交有關建築物或單位的負責人
- Copy of letter, e-mail or delivery note/receipt etc. to certify that the copy of Form of Compliance has been sent to the following administrator of the building concerned (please only select one) (see note 9):  
信函、電子郵件或發送單據/收據等的副本以證明有關遵行規定表格的文本已送交有關建築物的下列管理人 (請只選一項) (見須知事項9):
  - property management company  
物業管理公司
  - building owner (since no property management company can be ascertained then)  
建築物擁有人 (因為當時未能確定任何物業管理公司)
  - N/A (since no property management company can be ascertained then and the responsible person of the relevant building / units is also the building owner)  
不適用 (因為當時未能確定任何物業管理公司而有關建築物或單位的負責人亦是建築物擁有人)

(...continued on next page 接下頁)

**Please provide document proof**

# FOC (Cont'd)

## Form EE-SU



### Section C 丙部: Checklist of Documentary Proof that must be submitted 必須呈交的證明文件清單

I/we attach the copy of the following documentary proof (Must give a tick in all the appropriate boxes):  
本人/我們現附上以下證明文件的副本 (必須在所有適當空格加上✓號):

#### Only applicable to Form EE1 只適用於表格 EE1

- Copy of consent to the commencement of building works (see note 5)  
建築工程展開同意書的副本 (見須知事項5)
- Site location plan / map \* in A3 size  
A3尺寸之工地位置圖/地圖\*

#### Only applicable to Form EE2 只適用於表格 EE2

- Copy of occupation approval (see note 6)  
有關上蓋建築物之「佔用准許」的副本 (見須知事項6)

**No PMC and the responsible person of MRW  
is also the building owner**

#### Only applicable to Form EE4 只適用於表格 EE4

- Copy of letter, e-mail or delivery note/receipt etc. to certify that the Form of Compliance has been sent to the responsible person of the relevant building / units  
信函、電子郵件或發送單據/收據等的副本以證明有關遵行規定表格已送交有關建築物或單位的負責人
- Copy of letter, e-mail or delivery note/receipt etc. to certify that the copy of Form of Compliance has been sent to the following administrator of the building concerned (please only select one) (see note 9):  
信函、電子郵件或發送單據/收據等的副本以證明有關遵行規定表格的文本已送交有關建築物的下列管理人 (請只選一項) (見須知事項9):
  - property management company  
物業管理公司
  - building owner (since no property management company can be ascertained then)  
建築物擁有人 (因為當時未能確定任何物業管理公司)
  - N/A (since no property management company can be ascertained then and the responsible person of the relevant building / units is also the building owner)  
不適用 (因為當時未能確定任何物業管理公司而有關建築物或單位的負責人亦是建築物擁有人)

(...continued on next page 接下頁)



# FOC (Cont'd)

## Form EE-SU



(...continued from previous page 接上頁)

If no property management company, please arrange the representative of responsible person indicated in the associated Form of Compliance to endorse the following confirmation.

若無物業管理公司，請安排關聯的遵行規定表格所示的負責人之代表簽署以下確認。

Organization Name of Responsible Person# 負責人機構名稱#	English 英文	<b>ABC Company</b>
	Chinese 中文	
Name of Responsible Person's Representative# 負責人之代表名稱#	English 英文	<b>CHAN Tai Man</b>
	Chinese 中文	

(\*must be identical with the associated Form of Compliance 必須和關聯的遵行規定表格完全相同)


I, on behalf of the above responsible person, confirm that there was no relevant property management company at the time of issuing the associated Form of Compliance. I also declare that the above confirmation is true and correct.

本人謹代表上述負責人確認發出遵行規定表格之時並無有關的物業管理公司。本人亦聲明上述確認全屬真確無訛。

Signature  
簽署 **CHAN Tai Man**

Date  
日期 **01.12.2015**


Organization Chop  
機構蓋章



# FOC (Cont'd)



Figure 10.1.5.2 (b) : Schematic wiring diagram of retrofit



**Which one are complete circuit at 400A or above?**



# FOC (Cont'd)



For a works within an existing building, an REA signed and submitted all the following forms at the same time:

- EE1 – Stage One Declaration
- EE2 – Stage Two Declaration
- EE3 – Application for Renewal of COCR
- EE4 – FOC
- EE5 – Energy Audit Form (EUI left blank)
- EE-SU – Filling in works area of 400m<sup>2</sup>
- EE7 – Application for Duplication of COCR, FOC, EA Form

Is the building a prescribed building under the BEEO??



# Energy Audit Submission

珍惜資源  
全民節能

# Energy Audit submission (Cont'd)



Executive Summary of Energy Audit Report for Energy Audit Code (EAC)  
(Please refer to Section 8, Code of Practice for Building Energy Audit)

Form EE-EAes

Part 1 – Administrative Information & Building Characteristics		
(B) Building Characteristics (EAC Clause 8.1)		
(I) Building Type, Usage & Operation (Please click to select where applicable and insert N/A for non-applicable items.)		
1) Type of Building		
(a Please choose the type of building of the building entity <sup>^2</sup> audited:	Commercial building	
(b Please indicate the portion of the building entity being common area <sup>^4</sup> :	100.00%	
(c Please indicate the no. of blocks <sup>^2</sup> of the building entity:	1.00	no. of blocks
2) Total internal floor area <sup>^5</sup> of the building entity (m <sup>2</sup> ):	824.28	
3) No. of floors <sup>^6</sup> of the building entity:	7	
4) Major type of building façade:	Non-curtain wall	
5) Date(s) of issue of occupation approval (dd/mm/yyyy) <sup>^7</sup> :	11/4/1995	
	<input checked="" type="checkbox"/> Cool air	

Are all common areas?

OP date ?

Part 1 – Administrative Information & Building Characteristics		
(B) Building Characteristics		(EAC Clause 8.1)
(I) Building Type, Usage & Operation		(Please click to select where applicable and insert N/A for non-applicable items.)
1) Type of Building		
(a) Please choose the type of building of the building entity <sup>^2</sup> audited:	Commercial building	
(b) Please indicate the portion of the building entity being common area <sup>^4</sup> :	26.8%	
(c) Please indicate the no. of blocks <sup>^2</sup> of the building entity:	1	no. of blocks
2) Total internal floor area <sup>^5</sup> of the building entity (m <sup>2</sup> ):	36,510	
3) No. of floors <sup>^6</sup> of the building entity:	35	
4) Major type of building façade:	Curtain wall	
5) Date(s) of issue of occupation approval (dd/mm/yyyy) <sup>^7</sup> :	5/7/2001	
6) Type of central air-conditioning <sup>^8</sup> provided:	<input type="checkbox"/> Cool air <input checked="" type="checkbox"/> Chilled water <input type="checkbox"/> Condenser water <input type="checkbox"/> Not applicable	

- BEEO common area [sub-item 1)(b)]
  - buildings with “common area” – with Deed of Mutual Covenant (DMC) and separately owned units (Remark ^4)
  - buildings without “common area” – single ownership, “0” to be inserted, but still can have “commonly used areas” (see later slide)
- Total internal floor area of the building entity [item 2)]
  - To include tenant units area (Remark ^5), irrespective of CBSI served or non-served
- Central air-conditioning (AC) [item 6)]
  - 10% CBSI energy consumption criterion, may tick more than one sub-item (Remark ^8)

# Energy Audit submission (Cont'd)



## Form EE-EAes

Executive Summary of Energy Audit Report for Energy Audit Code (EAC)  
(Please refer to Section 8, Code of Practice for Building Energy Audit)

Form EE-EAes

Part 2 – Historical Energy Consumption Analysis <sup>A29</sup>					(EAC Clause 8.1(g))
1) Annual electricity consumption of last 36-month (kWh/annum) (EAC Clause 8.1(g)ii)	(kWh/annum)	(kWh/annum)	(kWh/annum)		
	Past 1 <sup>st</sup> 12-month	Past 2 <sup>nd</sup> 12-month	Past 3 <sup>rd</sup> 12-month		
2) Annual consumption of energy <sup>A30</sup> other than electricity, of last 36-month (MJ/annum) (EAC Clause 8.1(g)ii)	(MJ/annum)	(MJ/annum)	(MJ/annum)		
	Past 1 <sup>st</sup> 12-month	Past 2 <sup>nd</sup> 12-month	Past 3 <sup>rd</sup> 12-month		
3) Annual total energy consumption, of last 36-month (MJ/annum) (sum of figures in 1) & 2) <sup>A27E</sup> (EAC Clause 8.1(g)ii)	<b>A</b>				
	(MJ/annum)	(MJ/annum)	(MJ/annum)		
4) Annual Energy Utilisation Index (EUI) of last 36-month (MJ/m <sup>2</sup> /annum) <sup>A27E</sup> (EAC Clause 8.1(g)ii) (Value in kWh/m <sup>2</sup> /annum can be obtained by dividing the MJ/m <sup>2</sup> /annum figure by 3.6)	<b>B</b>				
	(MJ/m <sup>2</sup> /annum)	(MJ/m <sup>2</sup> /annum)	(MJ/m <sup>2</sup> /annum)		
5) Monthly EUI of past 1 <sup>st</sup> 12-month period (MJ/m <sup>2</sup> /month) (EAC Clause 8.1(g)iii)	1 <sup>st</sup> month	2 <sup>nd</sup> month	3 <sup>rd</sup> month	4 <sup>th</sup> month	<b>B</b>
	5 <sup>th</sup> month	6 <sup>th</sup> month	7 <sup>th</sup> month	8 <sup>th</sup> month	
	9 <sup>th</sup> month	10 <sup>th</sup> month	11 <sup>th</sup> month	12 <sup>th</sup> month <sup>A31</sup>	
6) Annual energy consumption breakdown, of past 1 <sup>st</sup> 12-month period (MJ/annum) (EAC Clause 8.1(g)iv)					<b>A</b>
	Air-conditioning <sup>A32</sup>	Lighting	Lift & Escalator	Others <sup>A33</sup>	